

# Water Study Group Meeting Well 11 Project Town of Hull Town Hall July 14, 2011

### **Presentation Outline**


- Introductions
- Brief History of Wisconsin Water Law
- ♦ Well 11 Project History & Background
- Area Water Level Data
- Local Groundwater Quality
- Well 11 Test Pumping Results
- Current Project Status
- Project Schedule
- Questions








# Well 11 Project History & Background North Well Field identified in the City's 1991 Water System Master Plan Majority of City water supply comes from Airport Well Field Well 10 recommended in 1991 and constructed in 1993 Horizontal Collector well similar to Well 11 Well yield = 5 mgd Close to the Plover River Very efficient, low drawdowns (1,250 gpm/ft) Very good water quality



















































### **Well 11 Project**

- Project in planning stages for 20 years
- Addresses current and future City water supply needs
- Addresses DNR recommendations to increase water supply capacity
- Provides supply reliability and improved water quality (e.g., Well 5 nitrate)
- City-owned property
- Very large aquifer saturated thickness
- Large separation distances from neighbors
- Large separation from Plover River

### **Well 11 Project Timeline**

- DNR well site approval February 2009
- ◆ DNR well engr report approval March 09
- PSC construction authorization April 09
- Public Hearing June 1, 2009
- → DNR well design approval July 2009
- State DNR funding approval August 2009
  - \$1.4 million grant; \$1.4 million loan
- State CDBG funding Sept 09 (\$750,000)



# Horizontal Collector Well


- Stevens Point Well 10
- Wisconsin Rapids Wells 1-4
- Calpine Power (Beloit)

# **Well 11 Project Timeline**

- Construction contract October 2009
- Construction start December 2009
- Caisson complete April 2010
- Laterals started May 2010
- Private wells inspected/sampled June 2010
- Laterals complete July 2010
- Meeting with Town WSG July 28, 2010
- Test pumping August 2010
- Well completed December 2010

### Well 11 Site Plan and Well Design

- Well 11 is a horizontal collector well very similar to City Well 10
- Collector wells:
  - Are more expensive to build
  - Have greater well yields
  - Have smaller local area water level drawdowns
  - Are more cost-effective when water treatment plants are required (economies of scale)




# Well 11 Site Plan


- WTP is being built next to well
- Temporary access road will be abandoned
- Permanent access road to STH 66
- New 24" water main along east ROW to Torun Road





### **Area Historical Water Levels**

- City has numerous monitoring wells the STH 66 and Airport area
- Monitoring wells sampled annually for water quality and for water depth
- Some wells indicate higher nitrate in shallow areas, and iron and manganese in deeper areas
- Groundwater levels do fluctuate seasonally and with extremely wet or dry conditions
- Private and high capacity well designs take these normal fluctuations into account when wells are constructed











# Anticipated Water Levels Affects July 2010 Site aquifer data collected in August 2007 and August 2008 Projections of water level impacts estimated based on 5 mgd pumping capacity • 12 hour per day pumping • No recharge for 30 continuous days Maximum drawdown within: → 200 feet is 3 feet Drawdown estimates are conservative


Drawdowns were measured during test pumping in August 2010


• 450 feet is 2 feet 1,400 feet is 1 foot













# **August 2010 Test Pumping Results**

- Well 11 was test pumped for 72 hours starting on August 16, 2010
- Well test pumped at 10,000 gpm, or 13 mgd
  - ◆ WTP design for 3,500 gpm (5 mgd) 38%
- Water levels monitored:
  - ♦ Well 11
  - ◆ Five on-site observation wells
  - ◆ Three City monitoring wells







# **Existing Groundwater Quality**

- Water quality on project site was sampled in August 2007, 2008 and 2010
- Groundwater meets all federal/state primary drinking water standards
- Groundwater meets all secondary (aesthetic) drinking water standards except:
  - ◆ Dissolved Iron: 0.42 mg/l 0.30 mg/l SMCL
  - ◆ Dissolved Manganese: 0.33 mg/l 0.05 mg/l

# **Groundwater Quality Impacts?**

- No significant changes are anticipated to the groundwater quality in the area
- Groundwater from Well 11 and from nearby private wells have already been tested
- County recommends all private well owners sample drinking water annually for bacteria and nitrate (\$44 at WEAL)

# How Will Any Future Changes in Groundwater Quality be Quantified?

- City has specific and frequent sampling requirements mandated by DNR
- June/July 2010 City paid to have Chet's Plumbing inspect and sample private wells within 1,400 feet of Well 11
- Confidential data collected:
  - Well type, depth, water level depth, well yield
  - Water quality WEAL Homeowners & Metals Package plus Total Dissolved Solids (~\$100 per well)

# Water Quality Sampling Established a Baseline of Data

- Water quality parameters tested by Water & Environmental Analysis Lab at UW-SP:
  - Alkalinity
  - Arsenic
  - Calcium
  - Chloride
  - Conductivity
  - Copper
  - Corrosivity Index
  - Hardness
  - IronLead
  - Magnesium

- Manganese
- Nitrate
- Nitrate + Nitrite
- pH (Lab)
- Potassium
- Sodium
- Sulfate
- ◆ Total Coliform Bacteria
- Total Solids
- Zinc

# General Water Quality Results Private Wells

- 44 private wells within 1,400 feet of Well 11 were sampled and tested at UWSP WEAL
- No unsafe samples for coliform bacteria
- 1 well tested >10 mg/l for nitrate (19.1 mg/l)
- pH ranged from 7.89 to 8.47
- 1 well water tested slightly corrosive
- No lead, arsenic, or copper concerns
- 4 wells with Fe >0.3 mg/l
- 1 well with Mn >0.05 mg/l (0.06 mg/l)

### Well 11 Project Status & Schedule

- Well pump station and treatment plant are currently being constructed on Cityowned property
- Pump station is built; WTP complete up to grade level
- Contractor plans to complete construction of buildings this Fall
- WTP to be completed early 2012 for testing and start up
- Facilities will be operational in 2012

